

15-135-20246-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

05-14-1969
RECEIVED
STATE CORPORATION COMMISSION
MAY 14 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Leben & McClure

Complete Address: 815 Wichita Plaza Wichita, Kansas

Lease Name Schogel Well No. 1

Location C SE SE Sec. 3 Twp. 19 Rge. (E) (W) 25

County Hess Total Depth 4443

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Leben Drlg.

Address: Wichita, Kansas License No.

Operation Completed: Hour 7:45P Day 11 Month 5 Year 1969

The Above well was plugged as follows:

RTD 4443' 8 5/8 csg set at 404' cwc Cmt. Lat. 50-50 poz cmt. 11/63 total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 390' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/14/69
INV. NO. 9762-4

Signed: Leo J. Murray
Well Plugging Supervisor