

R

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
02-02-1977
FEB 02 1977

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 21,288 - 0000 (Conservation Division well)

Operator's Full Name Donald C. Slawson
Complete Address 408-120 Bldg., Wichita, Kansas
Lease Name Humburg "B" Well No. 1
Location C NW NE Sec. 2 Twp. 19 Rge. (E) (W) 25
County Ness Total Depth 4500'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 12:45 P. Day 30 Month 1 Year 1977

The above well was plugged as follows:

RTD 4500' 8 5/8 csg set 404' cwc 250 sx. Plg. Mat. 50-50 poz 2% total gel.
Gunned pits, circulated heavy mud, set 50 sk cmt plug at 550' thru drill pipe.
Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Red Massey
Well Plugging Supervisor

DATE 2-2-77

NV. NO. 4577-W