

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

05-25-1976
MAY 25 1976

API Number 15 - 135 - 21,203 - 00-00 (of this well)

Operator's Full Name Lifestyle Engery Corp/

Complete Address 100 Nl. Central Expressway # 809, Richardson, Texas

Lease Name Wm. B. Baldwin Well No. 1

Location 100' E of G: NW SE Sec. 2 Twp. 19 Rge. (E) (W) 25

County Ness Total Depth 4492

Abandoned Oil Well Gas Well Input Well SWD Well D & A IX

Other well as hereafter indicated

Plugging Contractor Strata Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 10:15 P Day 21 Month 5 Year 1976

The above well was plugged as follows:

RTD 4492' 8 5/8 csg set 327' cwc Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Red Massey
Well Plugging Supervisor

DATE 5/27/76

INV. NO. 3250-W