

P

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135- 21,558-00-00 (of this well)

Operator's Full Name Chief Drlg. Co., Inc.

Complete Address 905 Century Plaza, Wichita, Ks.

Lease Name Spruill "A" Well No. 1

Location C W/2 W/2 NE Sec. 17 Twp. 19 Rge. (E) (W) 25

County Ness Total Depth 4501'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Warrior Drlg.

Address Wichita, Ks. License No.

Operation Completed: Hour 10:45 A Day 18 Month 3 Year 1979

The above well was plugged as follows:

RTD 4501' 8 5/8 csg set 300' cwc 200 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 270' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1979
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

3-20-79
9293-W