

15-135-20563-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202RECEIVED
STATE CORPORATION COMMISSION
FEB 2 1972
CONSERVATION DIVISION
Wichita, Kansas

02-02-1972

Operator's Full Name Leben, et al

Complete Address 200 W. Douglas Wichita, Kansas

Lease Name Spruil "C" Well No. 1

Location C SW NE Sec. 19 Twp. 19 Rge. (E) (W) 25

County Ness Total Depth 4552'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address Wichita, Kansas License No.

Operation Completed: Hour 9:30 A Day 30 Month 1 Year 1972

The above well was plugged as follows:

RTD 4552' 8 5/8 csg set at 416' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits; circulated heavy mud, set cementing plug at 720' and displaced 70 sk cmt thru drill pipe. Heavy mud to 360' set cementing plug and displaced 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug, 12 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed:

Well Plugging Supervisor

DATE 2-2-72INV. NO. 5111-W