

15-135-20123-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAR 13 1968
CONSERVATION DIVISION
Wichita, Kansas
03-13-1968

Operator's Full Name O. A. Sutton
Complete Address: 800 Sutton Place Wichita, Kansas
Lease Name Fitzgerald Well No. 1
Location C SE SW Sec. 22 Twp. 19 Rge. 25 (E) (W) X
County Ness Total Depth 4580'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Gabbert - Jones, Inc.
Address: Wichita, Kansas License No.
Operation Completed: Hour 11:15 A Day 10 Month 3 Year 1968

The Above well was plugged as follows:

RTD 4580' 8 5/8 csg set at 467' cwc 350 sc. Cem. Mat. 100 sc cem. W/ 6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 450' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Mosey
Well Plugging Supervisor

VOICED
3/13/68
7408-11