

15-135-20251-00-00

Form CP-3
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

05-26-1969
RECEIVED
STATE CORPORATION COMMISSION
MAY 26 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Tilco, Etal

Complete Address: 815 Wichita Plaza Wichita, Kansas 67202

Lease Name Fitzgerald "A" Well No. 1

Location C SE NW Sec. 26 Twp. 19 Rge. (E) (W) 25

County Ness Total Depth 4496

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Leb en Drlg.

Address: Wichita, Kansas License No.

Operation Completed: Hour 9:30A Day 25 Month 5 Year 1969

The Above well was plugged as follows:

RTD 4496' 8 5/8 csg set at 415' cwo Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 390' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of

cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. J. Musney
Well Plugging Supervisor

DATE 5/27/69
INV. NO. 9842-w