

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-135-00661-00-00

FILE NO. 18-21

LOCATION NW-SW-NE

SEC. 31 TWP. 19 RGE. 25W

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 3 Lease Bowman

Operator Loren W. Hallam Address Box 566 Salina Kans

Field _____ County Ness

Total Depth 4562 Feet.

Plugging Contractor H & O. Casing Pulling Co.

Plugging Contractor's License No. 206

Address Stafford Kans.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 13" @ 348' C.W.C. Oil string 5 1/2" @
4553 w/100 sq Cem. Filled with sand to 4540' and
dumped 5 sq Cem. shot off and pulled 5 1/2" casing
pumped in 25 sq of fresh fill mud, Plug, and
150 sq Cem. Pumped Cem to bottom of surface casing
filled hole with mud to 25' set a bridge and
10 sq of mixed Cem to base of cellar.

PLUGGING
FILE SEC 31 T 19 R 25W
BOOK PAGE 18 LINE 21

04-03-1954

Warren H. Harner
District Conservation Agent

Date April 1, 1954