

15-135-20879-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
04-25-1974
APR 25 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Murfin Drilling Company

Complete Address 617 Union Center, Wichita, Kansas

Lease Name Di Spirito Well No. 1

Location SE NW NE Sec. 31 Twp. 19 Rge. (E) (W) 25

County Ness Total Depth 4680' 4683

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Dunne-Gardner Petro., Inc.

Address Wichita, Kansas License No. _____

Operation Completed: Hour 1 P Day 21 Month 4 Year 1974

The above well was plugged as follows:

RTD 4680' 8 5/8 csg set at 405' cwo. Cmt. Mat. 50-50 poz W/6% total gel.

Gunned pits; circulated heavy mud, set cementing plug at 680' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Mussey
Well Plugging Supervisor

INVOICED

DATE 4/26/74

INV. NO. 9001-W