

15-135-20351:00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 2 1970

CONSERVATION DIVISION
Wichita, Kansas

07-02-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name R. V. Lehner

Complete Address box 398 Ness City, Kansas

Lease Name Schlegel Well No. 1

Location G NW NE Sec. 36 Twp. 19 Rge. (E) (W) 25

County Ness Total Depth 4490

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Strata Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 12:30 A Day 1 Month 7 Year 1970

The above well was plugged as follows:

RTD 4490' 8 5/8 csg set at 288' cwc Cmt. Mat. 100 sk reg poz 6%.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Richard Manning
Well Plugging Supervisor

7/2/70
2159-W