



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 9 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Buller of Gabbert Jones has this date requested permission to plug the following described well:

Mr. Buller guarantees payment of the plugging fee.

Operator's full Name: Rocket-Schusterman Oil Account

Complete Address: 1209 Mid Continent Bldg., Tulsa, Okla.

Lease Name: Hall "C" Well No. 3

Location: SE NW SW Sec. 36 Twp. 11 Rge. (E)(W) 17

County: Ellis Total Depth 3716 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Buller was instructed to plug the well as follows:

Gun pipe, circulate heavy mud, set cementing plug at 720' and displace
70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo. Z. Manning
Conservation Division Agent