

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 26 1972 6-26-72  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Clem Burton of Pickrell Drilling Company has this date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company, 2 SW Petro.-Chem.,

Complete Address: 705 4th National Bank Building, Wichita, Kansas.

Lease Name: Dumler Well No. U-3

Location: CSW-NW Sec. 11 Twp. 17 Rge. (E)(W) 26

County: Ness Total Depth 4519' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Burton was instructed to plug the well as follows:

270'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Dakota section @ 500'.

Circulate hole with heavy mud. Pull DP to 720' and displace 110 Cu. Ft.  
cement thru DP. Pull DP to 240' and displace 30 Cu. Ft. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to  
bottom of cellar.

Very truly yours,

W. L. Nichols  
Conservation Division Agent