

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 6 1972  
 CONSERVATION DIVISION  
 Wichita, Kansas

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Burton of Pickrell Drlg. has this date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co.

Complete Address: 705 Fourth Nat'l Bk. Bldg., Wichita, Kansas

Lease Name: Dumler "U" Well No. 2

Location: A/C NW NW Sec. 14 Twp. 17 Rge. (E)(W) 26

County: Ness Total Depth 4531' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Burton was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace  
70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and  
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Paul J. Miskay  
 Conservation Division Agent