

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water  
WICHITA, KANSAS 67202VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202JUN 20 1971  
CONSERVATION DIVISION  
WICHITA, KANSAS

Dear Sir:

Mr. Nelson of Blue Goose Drlg. has this

date requested permission to plug the following described well:

Mr. Nelson guarantees payment of the plugging fee.Operator's full Name: Mull Drlg. Co., Inc.Complete Address: 415 Page Ct., 220 W. Douglas, Wichita, Ks.Lease Name: Johnson Well No. 1Location: SE SW NW Sec. 18 Twp. 17 Rge. (E)(W) 26County: Ness Total Depth 4530' Oil Well Gas Well  Input Well  SWD Well  D & A XX Lost Hole Mr. Nelson was instructed to plug the well as follows:Gun pits, circulate heavy mud set 70 sk cmt plug at 720' thru drillpipe. Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavymud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

  
Conservation Division Agent