

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED  
STATE CORPORATION COMMISSION

SEP 10 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Continental Oil Company

Complete Address 3535 NW 58th Street Oklahoma City, Okla. 73112

Lease Name Warren Mortgage Investment Well No. 4

Location SE NE SE Sec. 3 Twp. 11 Rge. (E) (W) 18

County Ellis Total Depth 4173'

Abandoned Oil Well        Gas Well        Input Well        SWD Well XX D & A       

Other well as hereafter indicated       

Plugging Contractor Plainville Well Servicing

Address Plainville, Kansas License No.       

Operation Completed: Hour 4:30 P Day 7 Month 9 Year 1973

The above well was plugged as follows:

Total Depth 4173' 10 3/4 csg set at 204' cwc

6" csg set at 3793' cw 400 sk cmt.

6 -7 -71 Washed tubing down to 655' -pumped 20 sk gel W/4 sk hulls and 75 sk

60-40 poz. No returns -Fluid static at 35 ft.

9-7-73 Ran tbg to 60' (top of cement) pumped 215 sk cement W/500 lbs hulls -

filling 6" csg & anulus (10 3/4-6") to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Wassery  
Well Plugging Supervisor

DATE 9-10-73

INV. NO. 7893-W