

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 53-28 County: Ellis

Location: NW NE SW Sec. 3 Twp. 11 Rge. 18 (E) (W)

Name of Field: _____ Total Depth: 3536

I have this date completed supervision of plugging of:

Lease Name: Meistrell Well No. 1

Operator's Full Name: American Petrofina Co

Complete Address: Box 209 Russell, Kans

Plugging Contractor: C. E. Shull Casing Pulling Co

Address: Great Bend, Kans License No. 8

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 6PM Day 30 Month 7 Year 59

The above well was plugged as follows:

8 5/8" at 165' circulated with cement - 5 1/2" 3531' with 100 sax cement

hole in 5 1/2" at 763', pumped 150 sax cement on squeeze job, didnt

circulate - resqueezed with 100 sax cement 1300# pump pressure-

no pipe recovery.

Pumped hole full heavy mud (40 sax gel) pumped cementing plug followed

by 80 sax cement in 5 1/2" .

Mudding and cementing by Sun Cementing Co. 300# standing pump pressure.

Signed: *E. J. Little*
Conservation Division Agent

Reviewed: *J. Lewis Brock*
Field Supervisor

Remarks:

