

KANSAS

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 8 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Robert Kirk  
Complete Address 1519 Vickers KSB&T Bldg., Wichita, Kansas 67202  
Lease Name Mistrell "B" Well No. 1  
Location SE SE NW Sec. 3 Twp. 11 Rge. (E) (W) 18  
County Ellis Total Depth 3658'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Rockhold Engineering, Inc.  
Address Box 698 great Bend, Kansas 67530 License No. 670  
Operation Completed: Hour 11:30 A Day 2 Month 2 Year 1972

The above well was plugged as follows:

Total Depth 3670' 8 5/8 csg set at 189' cwc.  
5 1/2 csg set at 3610' cw 100 sk cmt.  
5 1/2 csg PBD 3558' and perf. (3412')  
Set 5 1/2 wood plug at 3350' -poured 10' sd -Dumped 5 sk cmt W/dump bailer. (3300-3350)  
Cutoff and recovered 713' of 5 1/2 csg.  
Pumped down 8 5/8 csg with 20 sk gel & water W/500 lbs hulls, -70 sk 50-50 poz cmt  
W/6% gel, -7 sk gel & water -released 8 5/8 plug and pumped 50 sk 50-50 poz cmt  
W/6% total gel, 300 lbs PSI.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ken J. Mancy  
Well Plugging Supervisor

DATE 12-1-71INV. NO. 4762-u