

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE NE NW

SEC. 3 TWP. 11 RGE. 18

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Warren

Operator National Co Op Refg Address Great Bend, Kans

Field _____ County Ellis

Total Depth 3683 Feet.

(Describe briefly the manner in which the well was plugged)

10" at 214' circulated with cement - 5 1/2" at 3628' with
75 sax cement behind - Lane Wells plugs to 3482' - Top perf
3450'.

Filled with chat to 3440', set 4 sax cement with dump bailer,
pulled 801' 5 1/2", filled with mud to 214', set rock and 20
sax cement, mud to 35', set rock and 10 sax cement to
bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUL - 2 1952
PLUGGING
FILE SEC 3 T 11 R 18
BOOK PAGE 14 LINE 23
CONSERVATION DIVISION
Wichita, Kansas

[Signature]
District Conservation Agent

Date 6-30-52