

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 28 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Beardmore Oil, Inc.

Complete Address 700 One Twenty Bldg., Wichita, Kansas

Lease Name Sargent "D" Well No. 1

Location NW SE Sec. 14 Twp. 17 Rge. (E) (W) 26

County Ness Total Depth 4492

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Rains & Williamson Oil.

Address Wichita, Kansas License No.

Operation Completed: Hour 7:30 A Day 26 Month 2 Year 1972

The above well was plugged as follows:

RTD 4492' 8 5/8 csg set at 286' cwc Cmt. Mat. 50-50 poz W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/28/72
INV. NO. 5242-11

Signed: Leo Massey
Well Plugging Supervisor