

KANSAS

*[Signature]*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 26 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Pickrell Drilling Company & SW Petro-Chem.,

Complete Address 705 Fourth National Bank Building, Wichita, Kansas.

Lease Name Dumler Well No. U-3

Location CSW-NW Sec. 14 Twp. 17 Rge. (E) (W) 26

County Ness Total Depth 4519'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Pickrell Drilling Company.

Address Above License No.       

Operation Completed: Hour 4:00 PM Day 23 Month 6 Year 1972

The above well was plugged as follows:

270'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 500'.

Circulated hole with heavy mud. Pulled DP to 720' and displaced 110 Cu. Ft. cement  
thru DP from 720' to 395'. Pulled DP to 240' and displaced 30 Cu. Ft. cement thru  
DP from 240' to 165'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *A. L. Nichols*  
Well Plugging Supervisor

INVOICE

DATE 6/29/72  
INV. NO. 5935-4