

15-135-20578-00-00

Form CP-3
Rev. 6-4-68

KANSAS

J
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 6 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company & Southwest Petro-Chem
Complete Address 705 Fourth National Bank Bldg., Wichita, Kansas
Lease Name Dumler "U" Well No. 2
Location A/C of NW NW Sec. 14 Twp. 17 Rge. (E) (W) 26
County Ness Total Depth 4531
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 1 P Day 3 Month 3 Year 1972

The above well was plugged as follows:

RED: 4531' 8 5/8 csg set at 252' cwc 150 sk. Cmt. Mat. 50-50 poz cmt W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INDEXED

Signed: Bio F. Murrain
Well Plugging Supervisor

DATE 3-6-72

INV. NO. 5301-11