

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Beardmore Oil, Inc.

Complete Address 700 One Twenty Bldg., Wichita, Kansas

Lease Name Fridell Well No. 1

Location C SE NE Sec. 14 Twp. 17 Rge. (E) (W) 26

County Ness Total Depth 4510'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Rains & Williamson

Address Wichita, Kansas License No.

Operation Completed: Hour 9:30 A Day 27 Month 10 Year 1972

The above well was plugged as follows:

RTD 4510' 8 5/8 csg set at 240' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk cmt
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Ben F. Wasey
Well Plugging Supervisor

INVOICED

DATE 11/1/72
INV. NO. 6557-W