

W
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Woodman & Iannitti
Complete Address: 706 Union Natl Bk Bldg Wichita, Kansas
Lease Name Moler Well No. 1
Location CSW SE Sec. 17 Twp. 17 Rge. (E) (W) 26
County Ness Total Depth 4520
Abandoned Oil Well Gas Well Input Well SWD Well D & A x
Other well as hereafter indicated:
Plugging Contractor: Forbes Casing Pulling Co
Address: Great Bend, Kans License No. 49
Operation Completed: Hour 5 PM Day 5 Month 8 Year 64

The Above well was plugged as follows:

8 5/8" 192' circulated with cement - 5 1/2" 4517' with 75 sax cement -
PB to 4502' - perf 4471'

Filled with sand to 4460', set 4 sax cement with dump bailer - pulled 700'
5 1/2" - circulated hole with heavy gel mud through 5 1/2" at 700' - displaced
20 sax cement through 5 1/2" at 700' - heavy mud to 180' - displaced 20
sax cement through 5 1/2" at 180', heavy mud to 55' - cement 55' to bottom
cellar.

Mudding and cementing by Forbes Pump Truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edon Perry*
Well Plugging Supervisor

DATE 8/10/64
INV. NO. 9626-W