

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

JUN 28 1977

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 135- 21,339-0000 (of this well)

Operator's Full Name Mull Drilling Company, Inc.  
Complete Address 415 Page Ct., 220 W. Douglas, Wichita, Kansas  
Lease Name Johnson Well No. 1  
Location SE SW NW Sec. 18 Twp. 17 Rge. (E) (W) 26  
County Ness Total Depth 4530'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor Blue Goose Drlg.  
Address Wichita, Kansas License No.         
Operation Completed: Hour 3:30 A Day 25 Month 6 Year 1977

The above well was plugged as follows:

RTD 4530' 8 5/8 csg set 286' cwc 180 sk. Plg. Mat. 50-50 poz 6% gel.  
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.  
Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6-28-77  
NO. 5401W

Signed: Leo Marney  
Well Plugging Supervisor