

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 3 1975  
CONSERVATION DIVISION  
WICHITA, KANSAS

Operator's Full Name Strata Drilling Co.

Complete Address Box 355, Great Bend, Kansas

Lease Name Scroggins Well No. 1

Location C SW SW Sec. 22 Twp. 17 Rge. (E) (W) 26

County Ness Total Depth 4464'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor        Co. Tools       

Address        License No.       

Operation Completed: Hour 4 P Day 31 Month 10 Year 1975

The above well was plugged as follows:

RTD 4464' 8 5/8 csg set 278' cwc 160 sk. Flg. Mat. 50-50 poz 2/3 total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 950' thru drill pipe.

Heavy mud to 270' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/3/75

INV. NO. 2166-W

Signed: Les Massey  
Well Plugging Supervisor