

15-135-20533-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Ness County. Sec. 6 Twp. 18S Rge. XXX 22 (W)
C SW SE

Location as "NE/CNW&SW" or footage from lines _____
Lease Owner Pickrell Drilling Company
Lease Name Stenzel "B" Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 24 19 71
Application for plugging filed December 24 19 71
Application for plugging approved December 24 19 71
Plugging commenced December 24 19 71
Plugging completed December 24 19 71
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4350 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	283'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug @ 660' w/70 sacks, Middle Plug @ 240' w/20 sacks,
Top Plug @ 40' w/10 Sacks.

RECEIVED
STATE CORPORATION COMMISSION
JAN 11 1972
CONSERVATION DIVISION
Wichita, Kansas

01-11-1972

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202


STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 Fourth National Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of December, 19 71

My commission expires January 19, 1973



Esther Lamone
Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Bldg.
Wichita, Kansas 67202

Rotary Drilling Commenced 12/15/71

Rotary Drilling Completed 12/24/71

LOCATION: Stenzel "B" No. 1, C SW SE Section 6-18S-22W
Ness County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: Run 7 Jts. 8-5/8" surface casing set @ 283' KB. Cemented
w/150 sacks. Completed 1:45 P.M. Circulated.

No oil string Run. D & A, Plugged down 10:00 P.M. December 24, 1971

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

65	Clay - Post Rock		
283	Cement, Shale, Sand Streaks	<u>C.F.S.</u>	
400	Shale	3710	4232
820	Shale & Sand Streaks	3768	4238
955	Red Bed & Shale	3865	4252
1150	Sand	3895	4272
1490	Shale	3915	4283
1526	Anhydrite	4015	4350
1640	Shale - Shells	4022	
2295	Shale	4050	
2800	Lime	4180	
2980	Lime & Shale		
3650	Shale & Lime		
3670	Shale		
3710	Lansing	<u>S.L.M.</u>	
3885	Lime	Strap 3710.00	
3920	Lime & Shale	Board 3708.54	
4230	Lime		1.46 Difference
4255	Lime & Chert		
4272	Miss. Chert & Lime		
4350	Miss., RTD		

Slope Tests

- 2000
- 2500
- 3000
- 3500
- 4000

RECEIVED
STATE CORPORATE COMMISSION
JAN 11 1972
CONSERVATION DIVISION
Wichita, Kansas
01-11-1972

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.


PICKRELL DRILLING COMPANY
By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 30th day of December, 19 71, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its attorney-in-fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.



My commission expires: January 19, 1973

Esther Lamone
Notary Public