


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Ness County. Sec. 22 Twp. 18S Rge. (E) 22 (W)
Location as "NE/CNW&SW" or footage from lines C SW SW
Lease Owner Pickrell Drilling Company
Lease Name Wegele "A" Well No. 2
Office Address 705 4th National Bank Bldg., Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 30, 1968
Application for plugging filed May 30, 1968
Application for plugging approved May 30, 1968
Plugging commenced May 30, 1968
Plugging completed May 30, 1968
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4312 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	257'	None


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 600'. Set plug. Cemented with 70 sacks cement. Heavy mud to 240'. Set plug. Cemented with 20 sacks cement. Heavy mud to 40'. Set plug. Cemented with 10 sacks cement to bottom of cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 6 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. SEBITS (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) C. W. SEBITS
705 4th National Bank Building, Wichita 2, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of June, 1968
L. M. Whiting, Notary Public.

My commission expires May 10, 1970

ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
705 4th National Bank Bldg.
Wichita, Kansas

Rotary Drilling Commenced 5/20/68

Rotary Drilling Completed 5/30/68

LOCATION: Wegele "A" No. 2, C SW SW Section 22-18S-22W, Ness County, Kansas.

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (13 jts) 8 5/8" surface casing set at 257', cemented with 165 sacks cement. Circulated. Completed 12:45 P.M. May 29, 1968. No oil string run. D & A plugged May 30, 1968.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

70	Post Rock & Clay	<u>C. F. S.</u>
257	Shale, Shells & Cement	
700	Shale & Shells	4210
815	Red Bed	4285
930	Shale & Red Bed	4312
1140	Sand	
1471	Shale	
1507	Anhydrite	
2200	Shale	<u>Slope Tests</u>
2385	Lime & Shale	2000
2700	Lime	2500
3330	Shale & Lime Stringers	3000
3645	Shale & Sandy Lime	3500
4210	Lime & Shale	4000
4243	Lime, Shale & Sand	
4312	Mississippian - TD	

S. L. M.

Strap 3949.06
Board 3948.92

.14

RECEIVED
STATE CORPORATION COMMISSION
JUN 6 1968
CONSERVATION DIVISION
Wichita, Kansas

06-06-1968

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By [Signature]
C. W. SEBITS Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 4th day of June, 1968, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 10, 1970

[Signature]
L. M. Whiting, Notary Public

