


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NESS County. Sec. 10 Twp. 18S Rge. ~~X/E~~ 22 (W)

Location as "NE/CNW/SW" or footage from lines C SW/4 SW/4
Lease Owner O. A. SUTTON
Lease Name MEHLER Well No. 1
Office Address 407 INSURANCE BLDG., WICHITA, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 3-15 19 63
Application for plugging filed PHONE 3-15-63 LETTER 3-19 19 63
Application for plugging approved 3-15 19 63
Plugging commenced 3-15 19 63
Plugging completed 3-15 19 63
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4399 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE HOLE		0	266	8-5/8"	266'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 220 FEET. SET FIRST PLUG AT 220 FEET WITH 40 SACKS CEMENT. FILLED HOLE WITH HEAVY MUD TO 40 FEET. SET SECOND PLUG AT 40 FEET WITH 10 SACKS OF CEMENT. CEMENTED BY GLOBE OILWELL CEMENTING, INC. PLUGGED RAT HOLE WITH 2 SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

MAR 21 1963

MAR 20 1963

CONSERVATION DIVISION
Wichita, Kansas

03-20-1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GABBERT-JONES INC.
Address 514 ORPHEUM BLDG., WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
E. E. HALL (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *E. E. Hall*

514 ORPHEUM BLDG., WICHITA, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 19TH day of MARCH, 19 63

My commission expires OCTOBER 2, 1963

Vina A. McKenzie
Notary Public.



15-135-19096-00-00

GARRETT-KNES INC.
WICHITA, KANSAS
DRILLERS WELL LOG

MEHLER #1
C SW SW SECTION 10-18S-22W
NESS COUNTY, KANSAS

COMMENCED: MARCH 5, 1963
COMPLETED: MARCH 16, 1963

OPERATOR - O. A. SUTTON

DEPTH		FORMATION	REMARKS
FROM	TO		
0	35	SURFACE CLAY	RAN 260,317 OF 8-5/8" CASING, SET @ 2661 W/ 200 SACKS CEMENT
35	266	SHALE & LIME	
266	730	SHALE	
730	760	SAND	
760	930	RED BED	
930	1200	SAND	
1200	1490	LIME & SHALE	
1490	1540	ANHYDRITE	
1540	3095	LIME & SHALE	
3095	3430	SHALE & SHELLS	
3430	3515	SHALE & SAND	
3515	3755	LIME & SHALE	
3755	3795	LIME	
3795	3865	SHALE & LIME	
3865	4131	LIME	
4131	4195	LIME & SHALE	
4195	4260	LIME	
4260	4305	LIME & SHALE	
4305	4311	LIME	
4311	4325	LIME & SHALE	
4325	4397	LIME & CHERT	
4397	4399	LIME	
4399	TD		DRY & ABANDONED

RECEIVED
STATE CORPORATION COMMISSION

MAR 20 1963

03-20-1963

CONSERVATOR OF DEEDS
Wichita, Kansas

I, E. E. HALL CERTIFY THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN C SW SW SECTION 10-18S-22W, NESS COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 19TH DAY OF MARCH, 1963, PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Vira A. McKenzie
VIRA A. MCKENZIE, NOTARY PUBLIC

MY COMMISSION EXPIRES OCTOBER 2, 1963.