

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-135-23,531-0000 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Bankoff Oil Company OPERATOR'S LICENSE NO. 6040

ADDRESS 100 S. Market, #203A, Wichita, KS 67202 PHONE # (316) 262-2784

LEASE (FARM) Carter A WELL NO. #1 WELL LOCATION C SW SW COUNTY Ness

SEC. 23 TWP. 17S RGE. 26 (E) or (W) TOTAL DEPTH 4494' PLUG BACK TO _____

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 331.89 CEMENTED WITH 60-40 pozmix SACKS 185

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS _____

PERFORATED AT _____

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Fill w/ heavy mud; set 1st plug @ 1880' w/50 sx; 2nd plug @

1100' w/50 sx; 3rd plug @ 590' w/50 sx; 4th plug @ 360' w/50 sx; 5th plug @ 40' w/10 sx;
Rathole 15 sx 60-40 pozmix 6% gel 1/4# Flocel.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? No
(If not explain.) Sent to Operator to complete

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 12-11-90 8:00 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: _____

Tony Martin PHONE # (913) 743-5443 1-11-91

ADDRESS 533 N. Main, Wakeeney, KS 67672

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack R. Whorton
(Operator or Agent)

DATE: January 10, 1991