

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-21973-00-00  
Spot: NENENWSE Sec/Twnshp/Rge: 11-16S-17W  
2525 feet from S Section Line, 1380 feet from E Section Line  
Lease Name: AARON ET AL Well #: 1-11  
County: RUSH Total Vertical Depth: 3611 feet

Operator License No.: 3882  
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN  
Address: 1515 WYNKOOP, STE 700  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	816		WITH 350 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/11/2012 12:00 AM  
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING  
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: 1ST PLUG AT 3520' WITH 50 SX CMT. 2ND PLUG AT 1110' WITH 30 SX CMT. 3RD PLUG AT 840' WITH 50 SX CMT. 4TH PLUG AT 420' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE  
Date/Time Plugging Completed: 05/11/2012 2:00 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

1ST PLUG AT 3520' WITH 50 SX CMT. 2ND PLUG AT 1110' WITH 30 SX CMT. 3RD PLUG AT 840' WITH 50 SX CMT. 4TH PLUG AT 420' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: DP

District: 01

RECEIVED  
MAY 17 2012  
KCC DODGE CITY

Signed

Kenny Sullivan  
(TECHNICIAN)

RECEIVED  
MAY 22 2012  
KCC WICHITA

Form CP-2/3