

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21572-00-00
Spot: NESWNWNW Sec/Twnshp/Rge: 33-30S-18W
945 feet from N Section Line, 525 feet from W Section Line
Lease Name: JELLISON Well #: 1-33
County: KIOWA Total Vertical Depth: 5610 feet

Operator License No.: 32781
Op Name: ROBERTS RESOURCES, INC.
Address: 2020 N TYLER RD, STE 106
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4780		WITH 2 SX CMT
CIBP		5250		
PROD	5.5	5606	1193	WITH 225 SX CMT
SURF	8.625	667		WITH 225 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 05/15/2012 8:30 AM
Plug Co. License No.: 34227 Plug Co. Name: AMERICAN WELL SERVICE LLC
Proposal Rcvd. from: KENT ROBERTS Company: ROBERTS RESOURCES Phone: (316) 215-1683

Proposed Plugging Method: CIBP @ 4780' WITH 2 SX CMT. PLUG AT 1110' WITH 15 SX GEL & 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 25 SX CMT

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE
Date/Time Plugging Completed: 05/15/2012 11:30 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 4780' WITH 2 SX CMT. 1ST PLUG AT 1100' WITH 17 SX GEL & 50 SX CMT. 2ND PLUG AT 700' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5482	5488		
5430	5434		
4802	4806		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed _____

[Handwritten Signature]
5/22/12
(TECHNICIAN)

RECEIVED
MAY 16 2012
KCC DODGE CITY

RECEIVED

MAY 22 2012
KCC WICHITA

Form CP-2/3

[Handwritten Initials]