

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-22147-00-00  
Spot: SWNENENW Sec/Twnshp/Rge: 30-23S-34W  
455 feet from N Section Line, 2020 feet from W Section Line  
Lease Name: HYLBOM A Well #: 3  
County: FINNEY Total Vertical Depth: 5062 feet

Operator License No.: 5447  
Op Name: OXY USA INC.  
Address: 5 E GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1816		WITH 460 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/19/2012 8:00 AM  
Plug Co. License No.: 34660 Plug Co. Name: AZTEC WELL SERVICING CO.  
Proposal Revd. from: DANIEL COOK Company: OXY USA Phone: (832) 405-2190

Proposed Plugging Method: 1ST PLUG AT 1850' WITH 50 SX CMT. 2ND PLUG AT 990' WITH 50 SX CMT. 3RD PLUG AT 450' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. NO RAT HOLE OR MOUSE HOLE.

Plugging Proposal Received By: DANIEL BERNASCONI Witness Type: NONE  
Date/Time Plugging Completed: 05/19/2012 5:00 PM KCC Agent: DANIEL BERNASCONI

Actual Plugging Report:

Perfs:

\*\*LOST CIRCULATION OF SURFACE PIPE. TOP OF 8 5/8" = 450'. RAN 1" TO 350'. PUMPED 46 BBLs CMT. CIRCULATED 4 BBL TO PIT.\*\* 1ST PLUG AT 1850' WITH 100 SX CMT. 2ND PLUG AT 975' WITH 50 SX CMT. 3RD PLUG AT 470' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. NO RAT HOLE OR MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: DP

District: 01

Signed

Daniel Bernasconi  
5/21/12

(TECHNICIAN)

RECEIVED

MAY 21 2012

KCC DODGE CITY

RECEIVED

MAY 22 2012

KCC WICHITA

Form CP-2/3

ROV