

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-10173-00-00
Spot: NWSWSWNE Sec/Twnshp/Rge: 6-27S-12W
2990 feet from S Section Line, 2337 feet from E Section Line
Lease Name: ICHU Well #: 4
County: PRATT Total Vertical Depth: 4317 feet

Operator License No.: 31739
Op Name: IUKA-CARMI DEVELOPMENT LLC
Address: PO BOX 847
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4193		
CIBP		4286		
PROD	4.5	4296	0	WITH 200 SX CMT
SURF	8.625	425		WITH 250 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 05/17/2012 9:30 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Revd. from: GARELD INSLEE Company: PRATT WELL SERVICE, INC. Phone: (620) 672-2531

Proposed Plugging Method: SAND 50' ABOVE PERFORATIONS & 5 SX CMT. PERFORATE @ 680' & CIRCULATE CMT UP ALL STRINGS OF PIPE.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/17/2012 10:55 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

SANDED BOTTOM TO 4100' & BAILED 5 SX CMT ON TOP OF SAND. FOUND CASING @ 2283'. SET CIBP @ 2210' WITH 2 SX CMT ON TOP OF PLUG. PERFORATED 4 1/2" @ 680'. PUMPED 275 SX CMT DOWN 4 1/2" CIRCULATING CMT TO SURFACE UP 8 5/8" X 4 1/2" ANNULUS. 5/18/12: CMT DOWN 100' INSIDE 4 1/2". CUT OFF SURFACE HEAD & FILL WITH REDIMIX.

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR RULE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

5/29/12

District: 01

Signed Richard W. Lacey

RECEIVED

MAY 21 2012

KCC DODGE CITY

(TECHNICIAN) RECEIVED

MAY 22 2012

KCC WICHITA

Form CP-2/3

ROWY