

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-21561-00-00  
Spot: E2NESW Sec/Twnshp/Rge: 22-22S-23W  
2007 feet from S Section Line, 2274 feet from W Section Line  
Lease Name: CLARENCE Well #: 1  
County: HODGEMAN Total Vertical Depth: 4619 feet

Operator License No.: 34318  
Op Name: BEREXCO LLC  
Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		1580		CEMENTED WITH 450 SX CMT. CMT CIRCULATED.
PROD	5.5	4612	0	WITH 250 SX CMT
SURF	8.625	270		WITH 175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/17/2012 11:30 AM  
Plug Co. License No.: 33369 Plug Co. Name: XTREME WELL SERVICE, INC.  
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO LLC Phone: (316) 772-8649

Proposed Plugging Method: SAND TO 4560' & 5 SX CMT. PLUG AT 1560' WITH 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT. CHECK BACKSIDE WITH 50 SX CMT TO 500 PSI.

Plugging Proposal Received By: DANIEL BERNASCONI Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/17/2012 1:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SANDED TO 4560' & 5 SX CMT. 1ST PLUG AT 1577' WITH 50 SX CMT. 2ND PLUG AT 615' WITH 50 SX CMT. 3RD PLUG AT 306' WITH 40 SX CMT. CIRCULATED TO SURFACE. CHECKED BACKSIDE WITH 10 SX CMT TO 300 PSI. PUMPED 5 SX CMT DOWN TOP. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4612	4618		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
MAY 21 2012  
KCC DODGE CITY

RECEIVED  
MAY 22 2012  
KCC WICHITA

5/31/12  
Form CP-2/3

AMZ