

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-24042-00-00  
Spot: NESESWSW Sec/Twnshp/Rge: 16-9S-19W  
335 feet from S Section Line, 1004 feet from W Section Line  
Lease Name: ARLENE Well #: 1  
County: ROOKS Total Vertical Depth: 3619 feet

Operator License No.: 30742  
Op Name: PALOMINO PETROLEUM, INC.  
Address: 4924 SE 84TH ST  
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	209		150 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/25/2012 12:00 AM  
Plug Co. License No.: 4958 Plug Co. Name: MALLARD, J. V., INC.  
Proposal Rcvd. from: CAROL Company: MALLARD, J. V., INC. Phone: (620) 241-4640

Proposed Plugging Method: Ordered 230 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: NONE  
Date/Time Plugging Completed: 05/25/2012 4:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Arbuckle Top @ 3524  
1st plug @ 3504 w/25 sx  
2nd plug @ 1480 w/25 sx  
3rd plug @ 820 w/100 sx  
4th plug @ 260 w/40 sx  
5th plug @ 40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: ALLIED

Plugged through: DP

District: 04

Signed Richard Williams  
6/15/12 (TECHNICIAN)

RECEIVED

JUN 04 2012

KCC WICHITA

Form CP-2/3

CM