

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-01529-00-01
Spot: SENV Sec/Twnshp/Rge: 8-28S-8W
3300 feet from S Section Line, 3300 feet from E Section Line
Lease Name: MALONEY OWWO Well #: 1
County: KINGMAN Total Vertical Depth: 3821 feet

Operator License No.: 31881
Op Name: MCGINNESS OIL COMPANY OF KANSAS
Address: 1700 N WATERFRONT PKWY, BLDG. 3
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3200		
PROD	4.5	3821		500 SX CMT
SURF	8.625	1172		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/23/2012 1:45 PM

Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.

Proposal Rcvd. from: BRAD TATRO Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC INSTRUCTIONS.

Plugging Proposal Received By: JEFF KLOCK

Witness Type: PARTIAL

Date/Time Plugging Completed: 05/23/2012 1:45 PM

KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3080'-CAPPED WITH 4 SX CEMENT. PERF CASING @ 1220'--750' & 250', RAN TUBING INTO 1220' SPOTTED 50 SX CEMENT, TAGGED PLUG @ 860'. RAN TUBING INTO 750' SPOTTED 25 SX CEMENT. PULLED TUBING TO 250' CIRCULATED TO SURFACE WITH 100 SX CEMENT, CEMENT CAME AROUND 4.5 INSIDE 8 5/8 S TO SURFACE. 5/24/12 CHECKED TOP PLUG ONLY DOWN 9 FEET.

Perfs:

Top	Bot	Thru	Comments
3658	3663		
3141	3146		
3132	3137		

Remarks: ALLIED CEMENT CO OUT OF GREAT BEND, TICKET #53617 -- 60/40 4% POS MIX. PAST 10 YEAR TA

Plugged through: TBG

District: 02

Signed B. J. Hope
6/16/12

(TECHNICIAN)

RECEIVED Form CP-2/3

JUN 04 2012

KCC WICHITA