

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23518-00-00
Spot: NWNESE Sec/Twnshp/Rge: 1-32S-6E
2270 feet from S Section Line, 945 feet from E Section Line
Lease Name: BROOKS Well #: 10
County: COWLEY Total Vertical Depth: 2200 feet

Operator License No.: 32475
Op Name: BRADEN, JAMES R. DBA BRADEN PET
Address: 10139 SW HAVERHILL RD
AUGUSTA, KS 67010

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2196	1220	125 SX
SURF	8.625	315		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/04/2012 8:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: AS PER KCC RULES & REGS / SAND BACK 50' ABOVE TOP PERF, & CAP W/CEMENT. CUT CASING & CIRCULATE TOP PLUG TO SURFACE.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 04/04/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/DUMP BAILOR TO TD, LAYED DOWN DUMP BAILOR. SANDED BACK @ 2075', DUMP BAILED 5 SXS CEMENT ON TOP. CUT CASING @ 1220', LAYED DOWN 1220' 5 -1/2" CASING. RIH W/2-3/8" TBG @365', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION & MIXED & PUMPED 111 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. CONSOLIDATED CEMENT TICKET #36093. PLUG DOWN 5:00 PM, 4-4-2012.

Perfs:

Top	Bot	Thru	Comments
2126	2136		CSG

Remarks: COMPLIANCE/ 10 YR RULE

Plugged through: TBG

District: 02

Signed

Duane Krueger
6/14/12 (TECHNICIAN)

RECEIVED
JUN 04 2012
KCC WICHITA

JK