

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19192-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 31-31S-7E
198 feet from S Section Line, 5080 feet from E Section Line
Lease Name: FG JABARA Well #: 3
County: COWLEY Total Vertical Depth: 2244 feet

Operator License No.: 32475
Op Name: BRADEN, JAMES R. DBA BRADEN PET
Address: 10139 SW HAVERHILL RD
AUGUSTA, KS 67010

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2243	1117	175 SX
SURF	10.75	127		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/27/2012 8:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: AS PER KCC RULES & REGS / SAND BACK 50' ABOVE TOP PERF, & CAP W/CEMENT. CUT CASING & CIRCUALTE TOP PLUG TO SURFACE.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE
Date/Time Plugging Completed: 03/27/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/DUMP BAILOR TO TD, LAYED DOWN DUMP BAILOR. SANDED BACK @ 2120', DUMP BAILED 7 SXS CEMENT ON TOP. CUT CASING @ 1117', LAYED DOWN 1117' 7" CASING. RIH W/2-3/8" TBG @ 365'. CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCUALTION & MIXED & PUMPED 200 SXS 60/40 POZMIX 4% GELTO SURFACE. CEMENT CIRCULATED. CONSOLIDATED CEMENT TICKET #36085. PLUG DOWN 5:00 PM, 3-27-2012.

Perfs:


Top	Bot	Thru	Comments
2173	2180		CSG

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed


6/14/12 (TECHNICIAN)

RECEIVED
Form CP-2/3
JUN 04 2012
KCC WICHITA

122