

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-23630-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 6-32S-7E
2959 feet from S Section Line, 2131 feet from E Section Line
Lease Name: FRANKS-BAIR-GOODRICH Well #: 1
County: COWLEY Total Vertical Depth: 2580 feet

Operator License No.: 32475
Op Name: BRADEN, JAMES R. DBA BRADEN PET
Address: 10139 SW HAVERHILL RD
AUGUSTA, KS 67010

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2579	1313	150 SX
SURF	8.625	302		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/09/2012 8:00 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: AS PER KCC RULES & REGS / SAND BACK 50' ABOVE TOP PERF, & CAP W/CEMENT. CUT CASING & CIRCULATE TOP PLUG TO SURFACE.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 04/09/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/DUMP BAILOR TO PBTD, LAYED DOWN DUMP BAILOR. SANDED BACK @ 2135', DUMP BAILED 5 SXS CEMENT ON TOP. CUT CASING @ 1313', LAYED DOWN 1313' 5-1/2" CASING. RIH W/2-3/8" TBG @ 365', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION & MIXED & PUMPED 117 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. CONSOLIDATED CEMENT TICKET # 34273. PLUG DOWN 5:00 PM, 4-9-2012.

Perfs:


Top	Bot	Thru	Comments
2186	2191		CSG

Remarks: COMPLIANCE - 10 YR RULE

Plugged through: TBG

District: 02

Signed


6/14/12 (TECHNICIAN)

RECEIVED
JUN 04 2012
KCC WICHITA