

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20982-00-00
Spot: SWNESW Sec/Twnshp/Rge: 25-29S-7W
1650 feet from S Section Line, 3300 feet from E Section Line
Lease Name: MILLARD Well #: 1
County: KINGMAN Total Vertical Depth: 5216 feet

Operator License No.: 8740
Op Name: BRAMWELL PETROLEUM, INC.
Address: 15183 SW 25TH AVE
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4209		250 SXS CMT
SURF	8.625	212		185 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/01/2012 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE Company: _____ Phone: (620) 532-6019

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 05/23/2012 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

3800' SET CIBP - CAPPED WITH 2 SX CEMENT. SHOT CASING OFF @ 1754' PULLED TO 1100' SPOTTED 50 SX CEMENT WITH 100 LBS OF HULLS, WAITED & TAGGED PLUG @ 821'. PULLED CASING TO 700' SPOTTED 35 SX CEMENT. PULLED CASING TO 260' CIRCULATED CEMENT TO SURFACE WITH 115 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
5154	5158		
4173	4175		
4133	4136		
4102	4116		
4097	4101		

Remarks: ALLIED FROM MEDICINE LODGE, KS -- PAST 10 YEAR TA

Plugged through: CSG

District: 02

Signed: B. J. Hope
6/14/12 (TECHNICIAN)

RECEIVED
JUN 04 2012 Form CP-2/3
KCC WICHITA