

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-30100-00-00
Spot: NESE Sec/Twnshp/Rge: 22-29S-8W
1980 feet from S Section Line, 660 feet from E Section Line
Lease Name: YOUNG K Well #: 1
County: KINGMAN Total Vertical Depth: 4621 feet

Operator License No.: 8740
Op Name: BRAMWELL PETROLEUM, INC.
Address: 15183 SW 25TH AVE
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4616	940	200 SX
SURF	8.625	207		155 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/01/2012 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE Company: Phone:

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX WitnessType: PARTIAL
Date/Time Plugging Completed: 05/21/2012 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 4120' CAPPED WITH 5 SX CEMENT. PERF CASING AT 1145'
SPOTTED 35 SX OF CEMENT WITH 100 LBS OF HULLS. SHOT CASING OFF @ 940'
PULLED CASING TO 800' SPOTTED 35 SX CEMENT. PULLED CASING TO 260'
CIRCULATED TO SURFACE WITH 100 SX OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
4245			
4241			
4236			

Remarks: ALLIED CEMENTING OUT OF GREAT BEND, KS - TICKET #53615

Plugged through: CSG

District: 02

Signed B. J. Hope
6/14/12 (TECHNICIAN)

RECEIVED
Form CP-2/3
JUN 04 2012
KCC WICHITA