

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20541-00-00
Spot: SENWNWNW Sec/Twnshp/Rge: 36-2S-30W
530 feet from N Section Line, 485 feet from W Section Line
Lease Name: ROGERS Well #: 4-36
County: DECATUR Total Vertical Depth: 4075 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4075		175 SX
SURF	8.625	628		400 SX
SURF	8.625	632		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/30/2012 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Revd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (800) 962-1206

Proposed Port Collar @ 2618'. T.O.C. 1000'.
Plugging Squeezed casing leaks from 2690' - 3169' w/225 sx.
Method: Production perforations: 3826'-3879'.
Ordered 450 sx 60/40 pozmix 4% gel cement w/1000 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/30/2012 1:50 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 2 holes @ 620'.
Ran tubing to 3792'. Swift services pumped 150 sx cement w/500 # hulls.
Pulled tubing to 2280'. Swift Services pumped 150 sxcement w/300 # hulls.
Pulled tubing to 800' and pumped 100 sx w/200 # hulls. Circulated cement.
Hooked to 8 5/8". Pumped 50 sx cement. Backside full. Hole below braden head.

Perfs:

Top	Bot	Thru	Comments
3875	3879		
3868	3870		
3843	3849		
3826	3829		

Remarks: SWIFT SERVICES. LEASE NAME ALSO KNOWN AS UNG #5-4

Plugged through: TBG

District: 04

Signed Richard Williams
6/15/12 (TECHNICIAN)

RECEIVED

JUN 04 2012

KCC WICHITA

MAY 31 2012

CM

Form CP-2/3