

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-017-20326-00-00
Spot: S2SESE Sec/Twnshp/Rge: 35-22S-9E
330 feet from S Section Line, 660 feet from E Section Line
Lease Name: ROBY Well #: 1
County: CHASE Total Vertical Depth: 2587 feet

Operator License No.: 5721
Op Name: GLACIER PETROLEUM CO., INC.
Address: 825 COMMERCIAL ST PO BOX 577
EMPORIA, KS 66801

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2576		100 SX
RBP		2490		
SURF	7	158		60 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/21/2012 12:00 AM
Plug Co. License No.: 5721 Plug Co. Name: GLACIER PETROLEUM CO., INC.
Proposal Rcvd. from: MARK LYNCH Company: _____ Phone: (620) 344-1471

Proposed Plugging Method: Set 50 ft. gravel and cement plug above top perf at 2473 ft., perf casing at approx 900 ft. and set 50 ft cement plug, perf casing at 208 ft. circ cement to surface

Plugging Proposal Received By: PATRICK SHIELDS Witness Type: PARTIAL
Date/Time Plugging Completed: 05/22/2012 9:00 AM KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

LOWER PERF CEMENTED OFF W/20 SX OF 60 X 40 4% GEL. CASING WAS PERFORATED @900' AND ALSO AT 208'. SET A 15 SX PLUG AT 900', TRIPPED OUT PIPE AND TIED ONTO CASING. ESTABLISHED CIRCULATION AND PUMPED 85 SX.

Perfs:


Top	Bot	Thru	Comments
2494	2506	TBG	
2476	2484	TBG	

Remarks: CONSOLIDATED TICKET #34693

Plugged through: TBG

District: 02

Signed


6/15/12

(TECHNICIAN)

RECEIVED
JUN 04 2012
KCC WICHITA