

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-06466-00-00  
Spot: SWSWE Sec/Twnshp/Rge: 5-18S-10W  
323 feet from S Section Line, 2314 feet from E Section Line  
Lease Name: ROESLER J Well #: 4  
County: RICE Total Vertical Depth: 3240 feet

Operator License No.: 9951  
Op Name: KRIER, KIRBY OIL, INC.  
Address: 1043 NE 80TH RD  
CLAFLIN, KS 67525

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| COND   | 0    | 0          |             | 0 SX     |
| PROD   | 5.5  | 3233       |             | 150 SX   |
| SURF   | 8.62 | 510        |             | 200 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/24/2012 1:00 PM  
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.  
Proposal Rcvd. from: FRED BECK Company: CLASSIC WELL SERVICE, INC. Phone: (620) 587-3402

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/24/2012 3:15 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 3180' AND CAP WITH 5 SX'S CEMENT. PERFORATE AT 1250', 900', AND 560'. RUN TUBING TO 1250' AND PUMP 70 SX'S CEMENT. PULL TUBING TO 900' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 560' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3233 | 3240 | OH   |          |

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C-39668. DENIED TA HIGH FLUID LEVEL

Plugged through: TBG

District: 02

Signed

Virgil Clothier  
6/15/12  
(TECHNICIAN)

RECEIVED

Form CP-2/3

JUN 04 2012

KCC WICHITA