

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-00005-00-00  
Spot: SWNWSE Sec/Twnshp/Rge: 1-32S-6E  
1638 feet from S Section Line, 2335 feet from E Section Line  
Lease Name: BROOKS Well #: 1  
County: COWLEY Total Vertical Depth: 2938 feet

Operator License No.: 32475  
Op Name: BRADEN, JAMES R. DBA BRADEN PET  
Address: 10139 SW HAVERHILL RD  
AUGUSTA, KS 67010

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	7	2200		
PROD	7	2889	1117	300 SX
SURF	10.75	128		125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/06/2012 8:00 AM  
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.  
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: AS PER KCC RULES & REGS / SAND BACK 50' ABOVE TOP PERF, & CAP W/CEMENT. CUT CASING & CIRCULATE TOP PLUG TO SURFACE.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/06/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/DUMP BAILOR TO PBTB, LAYED DOWN DUMP BAILOR. SANDED BACK @ 2075', DUMP BAILED 7 SXS CEMENT ON TOP. CUT CASING @ 1117', LAYED DOWN 1117' 7" CASING. RIH W/2-3/8" TBG @ 365', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION & MIXED & PUMPED 194 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. CONSOLIDATED CEMENT TICKET #34306. PLUG DOWN 5:00 PM, 4-6-2012.

Perfs:

Top	Bot	Thru	Comments
2889	2902		OH
2125	2144		CSG

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

District: 02

Signed

Duane Krueger  
6/04/12 (TECHNICIAN)

RECEIVED  
JUN 04 2012  
KCC WICHITA

JK