

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

X
API Well Number: 15-051-25501-00-00
Spot: SEWNENW Sec/Twnshp/Rge: 30-14S-20W
500 feet from N Section Line, 1880 feet from W Section Line
Lease Name: ADDIE Well #: 30-1
County: ELLIS Total Vertical Depth: 4000 feet

Operator License No.: 33335
Op Name: IA OPERATING, INC.
Address: 9915 W 21ST ST, STE B
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1570		
PROD	5.5	3995		150 SX CMT.
SURF	8.625	204		150 SX
TI	2.875	3816		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/24/2012 9:30 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: MIKE STANTON Company: IA OPERATING INC. Phone: (785) 689-8633

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 7 sx gel and 500 # hulls.
Port collar @ 1572' w/200 sx. Low fluid level.
Perforations: 3834'-3844' (marm), 3539'-3548'
PBTD-3955'

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/24/2012 11:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Quality rigged to 5 1/2" casing with a swedge, mixed and pumped 75 sx cement w/200# hulls mixed in; followed by 7 sx gell; followed by 200 sx cement w/300 # hulls mixed in. Pumped casing to pressure w/500 psi. Shut in pressure 400 psi.
Rigged to 8 5/8" casing. Pumped 5 sx cement to pressure w/200 psi. Shut in pressure 100 psi.

Perfs:

Top	Bot	Thru	Comments
3834	3844		
3539	3548		

Remarks: QUALITY OILWELL CEMENTING CO TICKET # 397

Plugged through: CSG

District: 04

Signed [Signature]
6/15/12 (TECHNICIAN)

RECEIVED CM
JUN 04 2012^m CP-2/3
KCC WICHITA

MAY 24 2012