

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-099-19942-00-00
Spot: SESENENW Sec/Twnshp/Rge: 31-31S-18E
4249 feet from S Section Line, 2576 feet from E Section Line
Lease Name: HARPER Well #: OW-1
County: LABETTE Total Vertical Depth: 849 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	0	0		0 SX
SURF	8.625	0		0 SX

Well Type: GAS UIC Docket No: Date/Time to Plug: 05/16/2012 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX ASHLOCK Company: Phone: (620) 365-3111

Proposed Plugging Method: WASH & DRILL DOWN TO FIND OLD TD. DRILL 2-4' OF NEW HOLE TO CONFIRM SAME. FILL FROM THAT DEPTH TO 500' W/CEMENT. THEN GEL SPACER - PULL UP HOLE TO 250' & PUMP CEMENT TO SURFACE. POOH W/DRILL PIPE AND TOP OFF W/CEMENT

Plugging Proposal Received By: WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/16/2012 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

Perfs:

Washed to 844' and drilled 5' of new hole. TD 849'. Gelled the well and pulled out. Ran back to TD and pumped cement from 849' to 500'. Pulled pipe to 250' and circulated cement to surface. Pulled remainder of pipe and topped off. Operator reported 196 sacks.

RECEIVED

JUN 05 2012 RH H

KCC Chanute Dist. #3

RECEIVED
JUN 07 2012
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Russell Hine
6/14/12 (TECHNICIAN)