


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Ness County, Sec. 2 Twp. 18S Rge. 26W (E) (W)
Location as "NE/CNW/SW" or footage from lines SE SE SE
Lease Owner William Gruenerwald
Lease Name Everett Well No. 1
Office Address Room 852, 35 E. Wacker Dr., Chicago, Ill.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed June 22 19 54
Application for plugging filed June 22 19 54
Application for plugging approved June 22 19 54
Plugging commenced 8:00 a.m., June 22 19 54
Plugging completed 12:00 noon, June 22 19 54
Reason for abandonment of well or producing formation
Commercial quantity of oil not found
If a producing well is abandoned, date of last production ---- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 4521 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	251'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 240' added 1/3 sack hulls. Pushed Halliburton plug to 235' - plug stopped with entire weight of drill pipe. Placed 20 sx cement - plug starting at 235' - filled with mud to 30 feet added 1/3 sack hulls - pushed plug to 30 feet with Kelly - Kelly stopped and plug took entire weight of Kelly and swivel - filled hole with 8 sx cement.

07-09-54

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor K & E Drilling, Inc.
Address 1006 Central Building, Wichita, Kansas


STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dale Silcott, agent for (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott
1006 Central Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8 day of July, 1954

My commission expires 10-29-55

Notary Public.



15-135-0007-0000

WILLIAM GRUENBERG
EVERETT NO. 2

SE SE Sec. -2-188-26W
Hess County, Kansas

Casing
5/8" Set @ 251'

Cement
170 sacks

Comp: 6-4-54
Comp: 6-22-54
Total Depth: 4521'

FORMATION	DEPTH
Surface soil and sand	0 - 200
Shale	200 - 251
Shale	251 - 430
Shale and shells	430 - 650
Sand and shale	650 - 790
Shale and shells - red bed	790 - 1300
Shale and shells and red bed	1300 - 1880
Anhydrite	1880 - 1905
Anhydrite	1905 - 1922
Shale and shells	1922 - 2300
Lime and shale	2300 - 2400
Lime and shale	2400 - 2770
Lime and sand	2770 - 2820
Lime and shale	2820 - 3250
Lime	3250 - 3285
Lime and shale	3285 - 3330
Lime and shale	3330 - 3390
Lime and shale	3390 - 3740
Blocky lime	3740 - 3770
Lime and shale	3770 - 3885
Lime	3885 - 4298
Lime and shale	4298 - 4329
Lime and shale	4329 - 4369
Lime and shale	4369 - 4441
Lime	4441 - 4466
Lime and shale	4466 - 4502
Unconsolidated	4502 - 4505
Mississippian	4505 - 4521

STATE OF KANSAS)
) SS
SEDGWICK COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

[Signature]

Subscribed and sworn to before me this 8 day of July, 1954.

[Signature]
Notary Public

My commission expires: 10-29-55

PLUGGING
HES SEC 2 T1N R24E
BOOK PAGE 111