

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-051-0034-0000
API NUMBER Spud 8/10/59

LEASE NAME Meistrell

WELL NUMBER ^{AWS KCC} 27 D-2

4290 Ft. from S Section Line

2210 Ft. from E Section Line

SEC. 9 TWP. 11 RGE. 18 (E) or (W)

COUNTY Ellis

Date Well Completed 8/59

Plugging Commenced 3/20/97

Plugging Completed 3/20/97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR DaMar Resources, Inc.

ADDRESS P. O. Box 70 Hays, KS 67601

PHONE#(913) 625-0020 OPERATORS LICENSE NO. 9067

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/20/97 (date)

by Herb Deines (Emergency plugging orders) (KCC District Agent's Name).

Is ACO-1 filled? ? If not, is well log attached? yes

Producing Formation Lansing Depth to Top 3289 Bottom 3511 T.D. 3667

Show depth and thickness of all water, oil and gas formations.

4-15-97

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	252	0
				5 1/2	3659	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforate @ 2050, 1480 and 750. Spot 100 sx cement w/200# hulls @ 3250'. Spot 100 sx cement w/200# hulls @ 2080'. Spot 50 sx cement w/100# hulls @ 780' to surface. Pump 10 sx cement down 5 1/2" casing @ 200#. Pump 65 sx cement w/200# hulls down 8 5/8 - 5 1/2 annulus, pressure up to 500#, shut in @ 200#. Cement is 60/40 poz w/10% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____

Address P. O. Box 31 Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: DaMar Resources, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.


Curtis R. Longpine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 70 Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 7th day of April, 1997

My Commission Expires: _____



[Signature]
Notary Public