

STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

KA-RC-62-3-111

API NUMBER October 1960

LEASE NAME Meistrell Unit

WELL NUMBER 1-1

4915 Ft. from S Section Line

2910 Ft. from E Section Line

SEC. 9 TWP. 11 RGE. 18 (E) or (W)

COUNTY Ellis

Date Well Completed Oct 1960

Plugging Commenced 4-12-93

Plugging Completed 4-12-93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Petroleum, Inc.

ADDRESS 301 North Main, Suite 900

PHONE#(316) 291-8200 OPERATORS LICENSE NO. 5238

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on April 12, 1993 (date)

by Hubert Dines (KCC District Agent's Name).

Is ACO-1 filed? No if not, is well log attached? Submitted with Form CP-1

Producing Formation L-KC Depth to Top 33021 Bottom 3398' T.O. 3655

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	257	None
				5 1/2	3652	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each section.  
5 1/2" csg. was originally cemented with a part collar @ 1380.56' cemented with 400sx poz. 4% gel cement circ. to surface on 9-14-60.  
Pumped 300sx 60/40 poz. 10% gel & 550# hulls down 2 7/8" tubing cement circulated S.I. casing pr. 1000#

Name of Plugging Contractor Allied Cementing Co., Inc. License No. \_\_\_\_\_

Address P.O. Box 342 Plainville, Kansas 67663

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Petroleum, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Paul Kreutzer

(Employee of Operator) or owner

above-described well, being first duly sworn on oath, says: That I have knowledge of the statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Paul Kreutzer APR 19 1993

(Address) 301 N. Main, Suite 900 Wichita, Kansas



TO before me this 16th day of April, 19 93

Sherry Fraser  
Notary Public

My Commission Expires: 3-20-94

USE ONLY ONE SIDE OF EACH FORM

Well Completed 9-30-60

FORM 578

# LANE WELLS Chlorinilog

A DIVISION OF DRESSER INDUSTRIES, INC

FILE NO.	COMPANY	PETROLEUM, INC.	MEISTRELL 1-1
	WELL	O'BRIEN "B" NO. 1	
	FIELD	MEISTRELL S.W.	
	COUNTY	ELLIS	STATE KANSAS
LOCATION:			Other Services
NE - NE - NW			
SEC	9	TWP	11 RGE 18

Permanent Datum	WELDED COLLAR	Elev.	2056	Elevations:
Log Measured from	WELDED COLLAR	5	Ft. Above Permanent Datum	KB 2061
Drilling Measured from	KELLY BUSHING			DF 2059
				GL 2056

Date	9-27-60
Run No.	1
Type Log	CHLORINILOG
Depth-Driller	3581
Depth-Logger	3593
Bottom Logged Interval	3592
Top Logged Interval	SURFACE
Type Fluid in Hole	WATER
Salinity Ppm Cl.	
Density lb./Gal.	
Level	1690
Max. Rec. Temp. Deg. F	
Opr. Rig Time	
Recorded By	BARLOW
Witnessed By	PROFFITT

Run No.	Bore Hole Record			Casing Record			
	Bit	From	To	Size	Wgt.	From	To
1	13-1/4	SURFACE	250	8-5/8	19.65	SURFACE	250
1	7-7/8	250	3655	5	14-3/4	SURFACE	3652

MAR 19 1993

CONSERVATION DIVISION  
Wichita, Kansas